BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2021-22/RD/WORK INDENT48383

NAME OF WORK: Filling of potholes in Bagalagunte in W.No 14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri PANDURANGA MALLAPPA,	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification & With all lead & lift charges & as per direction of Engineer-In-Charge of Work	Cum	861.84	130.0	Rupees One Hundred Thirty Only
2	Providing, laying, spreading and compacting cushed stone aggregates of granite / trap I basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve thedesired density complete as per specifications. & With all lead & lift charges & as per direction of Engineer-In-Charge of Work	Cum	660.74	1800.0	Rupees One Thousand Eight Hundred Only
3	Filling Pot-holes and Patch Repairs with Bituminous Concrete, 40 mm KSRRB M3000-5. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3, filling back the pot holes with hot bituminous material as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continuous surface, & With all lead & lift charges & as per direction of Engineer-In-Charge of Work	Sqm	2872.80	360.0	Rupees Three Hundred Sixty Only

ture of the Contractor,

Executive En
Dasarahalli D

4	Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications & With all lead & lift charges & as per direction of Engineer-In-Charge of Work	Cum	861.84	50.0	Rupees Fifty Only
5	Cost of Haulage Excluding Loading and Unloading & With all lead & lift charges & as per direction of Engineer-In-Charge of Work	km	861.84	20.0	Rupees Twenty Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,